

Laboratory Acoustical Test Report

FC21-0015

Impact Insulation Class and Sound Transmission Class

ASTM E492, E90

June 29, 2021

Test Assembly:

Maxxon Gypsum Concrete

Maxxon Acousti-Mat 1/4 Underlayment

2x10 Dimensional Lumber

CertainTeed R-13 Fiberglass Insulation

Cemco RC1-XD Resilient Channel

Pabco SoundCurb Type X

IIC-55

IIIC-53


STC-60

California Expanded Metal Company (CEMCO)

13191 Crossroads Parkway North Suite 325


City of Industry, CA 91746

Impact Insulation Class Test FC21-0015: IIC 55




Finish Flooring	n/a
Gypsum Topping	25 mm Maxxon Gyp-Crete® Gypsum Concrete
Sound Mat	6 mm Maxxon Acousti-Mat 1/4
Structural Sheathing	19 mm Plywood
Structure Type	235mm Dimensional Lumber
Insulation	89 mm CertainTeed R-13 Fiberglass Insulation
Resilient Attachment	13 mm CEMCO RC1-XD Resilient Channel
Finish Ceiling Layer 1	19 mm Pabco® Sound Curb™ Type X Gypsum Board

Test Date: February 16, 2021
 Construction Date: February 16, 2021
 Test Specimen Area: 11 sq.m.
 Receiving Room Volume: 158 cu.m.
 Receiving Room Temperature: 25.6-25.6 degrees C
 Receiving Room Relative Humidity: 56-57 percent




High-frequency Impact Insulation Class Test FC21-0015: HIIC 53




Finish Flooring	n/a
Gypsum Topping	25 mm Maxxon Gyp-Crete® Gypsum Concrete
Sound Mat	6 mm Maxxon Acousti-Mat 1/4
Structural Sheathing	19 mm Plywood
Structure Type	235mm Dimensional Lumber
Insulation	89 mm CertainTeed R-13 Fiberglass Insulation
Resilient Attachment	13 mm CEMCO RC1-XD Resilient Channel
Finish Ceiling Layer 1	19 mm Pabco® Sound Curb™ Type X Gypsum Board

Test Date: February 16, 2021
 Construction Date: February 16, 2021
 Test Specimen Area: 11 sq.m.
 Receiving Room Volume: 158 cu.m.
 Receiving Room Temperature: 25.6-25.6 degrees C
 Receiving Room Relative Humidity: 56-57 percent



Sound Transmission Class Test FC21-0015: STC 60



Finish Flooring	n/a
Gypsum Topping	25 mm Maxxon Gyp-Crete® Gypsum Concrete
Sound Mat	6 mm Maxxon Acousti-Mat 1/4
Structural Sheathing	19 mm Plywood
Structure Type	235mm Dimensional Lumber
Insulation	89 mm CertainTeed R-13 Fiberglass Insulation
Resilient Attachment	13 mm CEMCO RC1-XD Resilient Channel
Finish Ceiling Layer 1	19 mm Pabco® Sound Curb™ Type X Gypsum Board

Test Date: February 16, 2021


Construction Date: February 16, 2021

Test Specimen Area: 11 sq.m.

Source/Receiving Room Volume: 190/158 cu.m.

Source/Receiving Room Temperature: 19.6/18.6 degrees C

Source/Receiving Room Relative Humidity: 47/47 percent



Freq	TL
50	30
63	28
80	32
100	34
125	42
160	42
200	47
250	52
315	54
400	55
500	56
630	59
800	62
1000	63
1250	63
1600	63
2000	65
2500	67
3150	69
4000	71
5000	72
6300	74
8000	79
10000	81

Background Affected

Flanking Affected

Background and Flanking Affected

1.0 TEST PROCEDURES

1.1 Impact Insulation Tests

All tests were conducted in accordance with ASTM E492, "Standard Test Method for Laboratory Measurement of Impact Sound Transmission through Floor-Ceiling Assemblies Using the Tapping Machine." The IIC is a single-number rating derived from the Impact Sound Pressure Level in accordance with ASTM E989, "Standard Classification for Determination of Impact Insulation Class (IIC)." Results are presented above.

95% confidence intervals represent uncertainty for microphone averaging, not tapping positions.

1.2 High-frequency Impact Insulation Class Tests

The HIIC is the High-frequency Impact Insulation Class and is meant to assess the high-frequency impact noise on a floor-ceiling assembly. The higher the value, the better the floor, meaning less noise from high-frequency impacts in the space below.

All tests were conducted in accordance with the requirements of ASTM E492, "Standard Test Method for Laboratory Measurement of Impact Sound Transmission through Floor-Ceiling Assemblies Using the Tapping Machine," using ASTM E3222 "Standard Classification for Determination of High-frequency Impact Sound Ratings" to calculate the High-frequency Impact Insulation Class (HIIC). Results are presented above.

1.3 Transmission Loss Tests

All tests were conducted in accordance with ASTM E90, "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions," using the single-direction method. STC is a single-number rating derived from measured values of Sound Transmission Loss through a test specimen in accordance with ASTM E413, "Classification for Rating Sound Insulation." Results are presented above.



2.0 TEST ASSEMBLY

2.1 Assembly Description

The test assembly consists of:

- Maxxon Corporation Gyp-Crete®;
- Maxxon Corporation Acousti-Mat® 1/4;
- Plywood;
- CertainTeed R-13 Fiberglass Insulation;
- 2x10 Dimensional Lumber;
- CEMCO RC1-XD Resilient Channel;
- Pabco® Sound Curb™ Type X Gypsum Board.

Total mass of the floor-ceiling assembly was 954.5 kg, having an area density of 80.18 kg/m². This represents the entire area, which was separated into quadrants for the test.

Product/Element	Thickness	Dimensions	Area	Area Density
Maxxon Gyp-Crete®	25 mm	3023 x 3632	10.98 m ²	49 kg/m ²
Maxxon Acousti-Mat® 1/4	6 mm	3023 x 3632	10.98 m ²	0.3 kg/m ²
Plywood	19 mm	1219 mm x 2438 mm	10.98 m ²	10.25 kg/m ²
Fiberglass Insulation	89 mm	2940 mm x 406 mm	10.98 m ²	1.03 kg/m ²
Dimensional Lumber	235 mm	2940 mm x 38 mm	26.5 lin m	4.3 kg/m
CEMCO RC1-XD Resilient Channel	13 mm	3632 mm x 67 mm	32.69 lin m	0.34 kg/m
Gypsum Board	19 mm	1219 mm x 3023 mm	10.98 m ²	15.14 kg/m ²



2.2 Installation

The materials were installed in the following manner:

- Gypsum Concrete: Poured directly on top of the sound control mat, cured a minimum of 14 days. No noticeable shrinkage or cracking was visible on the specimen.
- Flooring underlayment: Loose laid with seams taped.
- Plywood: Fastened to joists with 76 mm by 3 mm framing nails on 203 mm centers along perimeter and 305 mm centers in the field.
- Fiberglass insulation: Stapled to bottom of subfloor.
- Dimensional Lumber: Fastened to perimeter frame on 406 mm centers using 18-gauge joist hangers and 9-gauge 31.75 mm nails.
- Resilient Channel: Installed on 406 mm centers perpendicular to the trusses. The measured thickness of the metal was 0.7 mm.
- Gypsum Board: Fastened with 25.4 mm fine thread drywall screws on 305 mm centers. Seams and perimeter sealed with Pecora AC-20® Acoustical Sealant and covered with pressure-sensitive tape.

The assembly was constructed on the test date February 16, 2021.



3.0 TESTING PROTOCOL

This report summarizes laboratory acoustical testing contracted by Veneklasen to be completed for California Expanded Metal Company (CEMCO) CEMCO RC1-XD Resilient Channel. The scope of the acoustical testing is for Impact Insulation Class (IIC), High-frequency Impact Insulation Class (HIIC), and Sound Transmission Class (STC), in accordance with ASTM standards E492, E90.

The tests were conducted on February 16, 2021. Details of the tests are contained in this report. Testing was completed in strict accordance with the following standards:

- ASTM E90, "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions"
- ASTM E413, "Classification for Rating Sound Insulation"
- ASTM E492, "Standard Test Method for Laboratory Measurement of Impact Sound Transmission through Floor-Ceiling Assemblies Using the Tapping Machine"
- ASTM E989, "Standard Classification for Determination of Impact Insulation Class (IIC)"
- ASTM E2235, "Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods"
- ASTM E3222, "Standard Classification for Determination of High-frequency Impact Sound Ratings."

3.1 Equipment

Equipment list and information associated with this test, including calibration information, is included in the Appendix.

3.2 Accreditation and Reporting

Report must be distributed in its entirety except with written authorization from Veneklasen Associates. Test was conducted at IAS-accredited test facility; the full report is available upon request. Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available on request.

Veneklasen Associates provides no warranties, expressed or implied, regarding the structural integrity or fitness of these assemblies for a specific installation. Any advertising which utilizes this test report or test data must not imply product certification or endorsement by Veneklasen Associates, NVLAP, NIST or the U.S. Government.

Sincerely,
Veneklasen Associates, Inc.

John LoVerde, FASA
Principal

APPENDIX

Test Equipment and Photos



Instrument	Manufacturer	Model	Description	Serial Number	Calibration Date
Data acquisition unit	National Instruments	PXI-4462	Data acquisition card	65124	12/18
Data acquisition unit	National Instruments	PXI-4462	Data acquisition card	INT01524	04/19
Data acquisition unit	National Instruments	PXI-4462	Data acquisition card	INT01525	04/19
Microphone calibrator	Norsonic	1251	Acoustical calibrator	65105	09/20
Receive room microphone	PCB Piezotronics	378C20	Microphone and preamplifier	65029	03/20
Receive room microphone	PCB Piezotronics	378B20	Microphone and preamplifier	63742	03/20
Receive room microphone	PCB Piezotronics	378B20	Microphone and preamplifier	65968	01/21
Receive room microphone	PCB Piezotronics	378B20	Microphone and preamplifier	63740	04/20
Receive room microphone	PCB Piezotronics	378B20	Microphone and preamplifier	63739	04/20
Receive room environmental indicator	Comet	T7510	Temperature and humidity transmitter	63810	10/20
Source room microphone	PCB Piezotronics	378C20	Microphone and preamplifier	63741	06/20
Source room microphone	PCB Piezotronics	378C20	Microphone and preamplifier	65969	04/20
Source room microphone	PCB Piezotronics	378C20	Microphone and preamplifier	63747	09/20
Source room microphone	PCB Piezotronics	378C20	Microphone and preamplifier	63745	09/20
Source room microphone	PCB Electronics	378C20	Microphone and preamplifier	63744	09/20
Source room environmental indicator	Comet	T7510	Temperature and humidity transmitter	63812	10/20
Tapping machine	Norsonic	Nor277	Tapping Machine	INT00936	01/20
Test Chamber Receive Room Volume			157.83 m ³ (5573.68 ft ³)		
Test Chamber Source Room Volume			190 m ³ (6709.79 ft ³)		



Photo 1: View of Source Chamber, finish flooring installation observed



Photo 2: View of Receive Chamber